

## POWER DIST PANEL 75KVA

Unit will consist of the following

- A welded and powder coated free standing steel frame.
- A 225 amp, 600 volt 4 wire 4 pole splitter.
- A 75 KVA transformer, 3 phase dual primary, 600/480 – 120/208.
- A 100 amp, 600 volt safety switch, fused at 70 amps. (Transformer primary).
- 3 – 60 amp, 600 volt safety switches. (Primary voltage distribution).
- A 200 amp, 250 volt load center, 30 circuits.
- A 24 outlet receptacle enclosure, c/w wet locations cover.
- 20 – 15/20 amp, 125 volt GFCI receptacles.
- 2 – 50 amp, 125/250 volt twist lock receptacles
- 2 – 30 amp, 125/250 volt twist lock receptacles.



**TCRS model: 75 KVA LV3**

All temporary power units will be completely wired, tested and CSA approved; NEMA 3R outdoor use.